27	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, Complete as per Specification.	No's	2.00	264.00	Rupees Two Hundred Sixty Four Only
28	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's. Complete as per Specification.	No's	2.00	1350.00	Rupees One Thousand Three Hundred Fifty Only
29	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc., Complete as per Specification.	No's	4.00	1430.00	Rupees One Thousand Four Hundred Thirty Only
30	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Complete as per Specification.	No's	2.00	302.50	Rupees Three Hundred Two and Fifty Paise Only
31	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods Complete as per Specification.	Cum	108.00	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
32	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., Complete as per Specification.	Mtr	200.00	324.36	Rupees Three Hundred Twenty Four and Thirty Six Paise Only
33	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour Complete as per Specification.	Cum	108.00	59.36	Rupees Fifty Nine and Thirty Six Paise Only

Note: The said work for sanctioned estimate cost Rs.15.00 Lakhs (Rupees Fifteen Lakhs Only) (Incl.10%+1%KRIDL Charges + 1% Quality control tests Charges) based On "Approved SR Rates"

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, Bangalore

Executive Engineer,
Dasarahalli Division,